## NO. GENERAL NOTES (WATER AND SEWER)

- 1. APPROVAL OF THESE PLANS BY RMWD IS VALID FOR A PERIOD OF TWO YEARS FROM THE DATE WHICH THE DISTRICT SIGNS THE PLANS. AFTER TWO YEARS, RESUBMITTAL IS REQUIRED.
- 2. APPLICATION FOR WATER AND/OR SEWER SERVICE WILL NOT BE PROCESSED UNTIL A NOTICE OF COMPLETION HAS BEEN FILED WITH THE COUNTY RECORDER'S OFFICE AND DEDICATION ACCEPTED BY THE DISTRICT.
- 3. ADDITIONAL FACILITIES AND CONSTRUCTION THAT IS DETERMINED NECESSARY IN THE COURSE OF CONSTRUCTION SHALL BE PROVIDED BY THE DEVELOPER AT ITS OWN EXPENSE.
- 4. THE CONTRACTOR SHALL CONFORM TO LABOR CODE SECTION 6205 BY SUBMITTING A DETAILED PLAN SHOWING THE DESIGN OF SHORING, BRACING, SLOPING OR OTHER PROVISIONS TO BE MADE FOR WORK PROTECTION FROM THE HAZARD OF CAVING GROUND DURING THE EXCAVATION OF SUCH TRENCH OR TRENCHES OR DURING THE PIPE INSTALLATION THEREIN. THIS PLAN MUST BE PREPARED FOR ALL TRENCHES FIVE FEET OR MORE IN DEPTH AND APPROVED BY THE OWNER PRIOR TO EXCAVATION. IF THE PLAN VARIES FROM THE SHORING SYSTEM STANDARDS ESTABLISHED BY THE CONSTRUCTION SAFETY ORDERS, THE PLAN SHALL BE PREPARED BY A REGISTERED CIVIL ENGINEER OR STRUCTURAL ENGINEER AT THE CONTRACTOR'S EXPENSE.
- 5. CONTRACTOR TO PROVIDE CONSTRUCTION STAKING AND THREE (3) SETS OF CUT SHEETS TO THE INSPECTOR 24 HOURS PRIOR TO EXCAVATING.
- 6. ALL WORK TO BE PERFORMED IN CONFORMANCE WITH THE STANDARD DRAWINGS AND SPECIFICATIONS OF THE WATER AGENCY STANDARDS (WAS) AND WILL BE ACCEPTED UPON APPROVAL FROM RAMONA MUNICIPAL WATER DISTRICT (RMWD).
- 7. STANDARD SPECIFICATIONS AND DRAWINGS OF THE WATER AGENCY STANDARDS FOR WATER AND SEWER MAIN CONSTRUCTION ARE AVAILABLE AT: HTTP://WWW.SDWAS.COM
- 8. NO FIELD CHANGES OR REVISIONS SHALL BE MADE TO THESE PLANS WITHOUT THE WRITTEN APPROVAL OF THE R.M.W.D. DISTRICT ENGINEER AND ENGINEER OF WORK.
- 9. APPROVAL OF THIS PLAN BY R.M.W.D. DOES NOT CONSTITUTE A REPRESENTATION AS TO THE ACCURACY OF THE LOCATION OF, OR THE EXISTENCE OR NONEXISTENCE OF ANY UNDERGROUND WATER, SEWER, OR UTILITY PIPE OR STRUCTURE WITHIN THE LIMITS OF THIS PROJECT.
- 10. CONTRACTOR TO LOCATE ALL EXISTING UNDERGROUND UTILITIES AND NOTIFY THE DISTRICT AT LEAST 5 WORKING DAYS AHEAD OF CONSTRUCTION TO PERMIT REVISIONS AS NECESSARY BECAUSE OF ACTUAL LOCATION OF EXISTING FACILITIES.

- 11. CONTRACTOR TO MEET INSPECTOR BEFORE STARTING WORK, GIVE 72 HOUR NOTICE.
- 12. CONTRACTOR SHALL KEEP A SET OF REDLINE AS-BUILTS ON THE SITE AT ALL TIMES AND UPDATE DAILY.
- 13. CONTRACTOR SHALL SUBMIT THE REDLINE AS-BUILTS TO THE ENGINEER OF WORK ONCE THE PROJECT HAS BEEN COMPLETED.
- 14. ENGINEER OF WORK TO PROVIDE AS-BUILT PLANS (MYLAR AND ELECTRONIC) TO THE DISTRICT UPON COMPLETION OF THE PROJECT.
- 15. CONTRACTOR TO NOTIFY UNDERGROUND SERVICE ALERT AT 1-800-422-4133. CALL A MINIMUM OF TWO WORKING DAYS PRIOR TO EXCAVATION.
- 16. CONTRACTOR TO OBTAIN ALL PERMITS.
- 17. CONTRACTOR TO PROIVDE AND INSTALL ALL MATERIAL, WHICH SHALL BE NEW.
- 18. THE CONTRACTOR SHALL AND HEREBY DOES GUARANTEE ALL WORK TO BE FREE OF DEFECTS IN WORKMANSHIP AND/OR MATERIALS FOR A PERIOD OF ONE YEAR AFTER THE DATE OF NOTICE OF COMPLETION FILED BY THE DISTRICT AND SHALL REPAIR OR REPLACE ANY OR ALL SUCH WORK, TOGETHER WITH ANY OTHER WORK WHICH MAY BE IMPACTED AT NO COST TO THE DISTRICT.
- 19. JOB MIXING OF CONCRETE WILL NOT BE ALLOWED WITHOUT THE PRIOR PERMISSION OF THE DISTRICT.
- 20. ALL CONCRETE TESTING REQUIRED BY THE DISTRICT WILL BE AT THE EXPENSE OF THE CONTRACTOR.
- 21. SOILS REPORTS SHALL BE SUBMITTED TO THE ENGINEER OF WORK AND THE DISTRICT BY A QUALIFIED SOILS ENGINEER WHICH CERTIFIES THAT TRENCH BACK FILL WAS COMPACTED IN ACCORDANCE WITH DISTRICT SPECIFICATIONS OR ONSITE EARTHWORK SPECIFICATIONS, WHICHEVER IS MORE RESTRICTIVE.
- 22. PROJECT WILL NOT BE ACCEPTED UNTIL ROAD IS RESTORED TO ITS ORIGINAL CONDITION OR BETTER, OR TO THE CONDITION SPECIFIED BY THE COUNTY OR STATE.
- 23. RELATIVE COMPACTION AROUND FACILITIES SHALL CONFORM TO STANDARD SPECFICATION SECTION 02223.
- 24. WARNING/IDENTIFICATION TAPE BURIED 12" ABOVE TOP OF PIPE AS SHOWN IN STANDARD DRAWING WP-02 & SP-01.
- 25. ALL PIPE SHALL HAVE A MINIMUM 6-INCH BEDDING THICKNESS AS SHOWN ON STANDARD DRAWING WP-02 AND SP-03. PIPE ZONE MATERIAL SHALL CONFORM TO THE GRADATION IDENTIFIED IN STANDARD SPECIFICATION SECTION 02223.
- 26. CONTRACTOR TO HAVE ALL FITTINGS AND PIPE MATERIALS INSPECTED PRIOR TO START OF CONSTRUCTION.

- 27. PLACEMENT OF A WATER AND/OR SEWER SERVICE LATERAL ON THE PLANS DOES NOT ENSURE THAT WATER OR SEWER SERVICE WILL BE APPROVED OR PROVIDED BY THE DISTRICT.
- 28. CONTRACTOR SHALL POSSESS A CLASS 'A' CONTRACTORS LICENSE FOR WORK ON WATER AND SEWER PIPELINE INSTALLATIONS IN CONFORMANCE WITH THE CALIFORNIA CONTRACTOR'S LICENSE LAW AND W.A.S. SPECIFICATION SECTION 01000 SUBSECTION 1.02.