

NO.	WATER NOTES
1.	CONTRACTOR SHALL DISINFECT THE PIPELINE ACCORDING TO SECTION 15041 OF SPECIFICATIONS.
2.	CONTRACTOR TO SET MARKER AND PROTECTIVE POSTS ACCORDING TO SECTION 09910 OF THE SPECIFICATIONS.
3.	CONTRACTOR TO PROVIDE THE DISTRICT 48 HOURS ADVANCED NOTICE TO SCHEDULE SHUT-DOWN. DATE TO BE DETERMINED BY THE DISTRICT.
4.	DUCTILE IRON FITTINGS SHALL BE IN ACCORDANCE WITH SECTION 15056 OF THE SPECIFICATIONS
5.	ALL WET TAPS SHALL BE MADE BY THE DISTRICT AND SHALL NOT BE DONE ON MONDAY OR FRIDAY.
6.	ALL PIPE TO BE CL-200 PVC (C-900) IN ACCORDANCE WITH SECTION 15064 OF THE SPECIFICATIONS UNLESS APPROVED BY DISTRICT.
7.	ALL WATER METER SERVICES SHALL BE MINIMUM 1-INCH COPPER (FLARE TYPE).
8.	CONTRACTOR TO USE SINCLAIR SINTEC #7571 OSHA YELLOW FOR ALL FACILITIES NEEDING YELLOW PAINT IN ACCORDANCE WITH SECTION 09910 OF THE SPECIFICATIONS.
9.	CONTRACTOR TO USE SINCLAIR SINTEC #7575 OSHA PURPLE FOR ALL FACILITIES NEEDING PURPLE PAINT IN ACCORDANCE WITH SECTION 09910 OF THE SPECIFICATIONS.
10.	BEFORE A SHUT-DOWN WILL BE SCHEDULED, CONTRACTOR SHALL POT HOLE TO VERIFY EXISTING PIPE MATERIAL AND SIZE.
11.	CONTRACTOR IS RESPONSIBLE FOR PROPER HANDLING AND STORAGE OF ASBESTOS-CEMENT PIPE (ACP) IN CONFORMANCE WITH SPECIFICATION SECTION 15000 SUBSECTION 3.15.
12.	INSTALL INSULATED TRACER WIRE PER SECTION 15000 OF THE SPECIFICATIONS AND WP-01 OF THE STANDARD DRAWINGS.
13.	THRUST BLOCKS HAVE BEEN SIZED WITH AN ASSUMED SOIL CONDITION OF (ENGINEER TO ENTER SOIL TYPE AND ALLOWABLE BEARING PRESSURE) . IF CONTRACTOR SHOULD ENCOUNTER SOIL CONDITIONS OTHER THAN THAT ASSUMED, THEN THE RMWD INSPECTOR AND DESIGN ENGINEER SHALL BE NOTIFIED IMMEDIATELY. THRUST BLOCKS SHALL NOT BE INSTALLED UNTIL A NEW THRUST BLOCK SIZE HAS BEEN DETERMINED BY THE ENGINEER OF WORK AND APPROVED BY RMWD ENGINEERING STAFF.
14.	SACRIFICIAL ANODES SHALL BE INSTALLED ON ALL COPPER TUBING PER WAS STD DWG WC-17 AND SPECIFICATION SECTION 13110.
15.	A REDUCED PRESSURE PRINCIPLE BACKFLOW PREVENTION DEVICE SHALL BE INSTALLED ON ALL WATER SERVICE LATERALS IN ACCORDANCE WITH THE APPROVED MATERIALS LIST AND WR-01 OR WR-02 OF THE STANDARD DRAWINGS. PRIOR TO CONSTRUCTION, THE CONTRACTOR SHALL CONTACT THE RMWD WATER RESOURCES SPECIALIST AT 760-789-1330 FOR ADDITIONAL INFORMATION.